

Public Works – Scheduled Capital Project

PROJECT TITLE: Kirkwood Drainage

Project Description: This project proposes to construct a storm drain system to relieve localized flooding at SW 25th Place. Runoff currently ponds in a depressional area north of SW 25th Place, overtopping the roadway during higher storm events. The runoff travels south via overland flow to East Tumbler Creek. The storm drain system will begin at the local depression on the north side of SW 25th Place and outfall at East Tumbler Creek. The storm drain alignment will be placed in an existing 20-foot wide easement between two (2) residential parcels south of the roadway. Ditch bottom inlets (DBIs) will be placed on both sides of SW 25th Place to collect stormwater at the depressional area. The storm drain system will provide a stable conveyance to East Tumbler Creek. The system will be designed to convey the 100-year storm event without flooding SW 25th Place.



A consultant, Johnson, Mirmiran, & Thompson (JMT) was hired to develop construction plans, permits, and contract documents for the project. No environmental impacts are anticipated. The City of Gainesville intends to select a contractor to construct the project.

- Size: TBD
- Total Project Funding: \$3,978 (Design only)
- Funding Source: Hazard Mitigation Grant Program
- Planning Phase: Complete
- Pre & Landscape Design: Complete
- Building Design: Not Applicable
- Initial Design Contract: Not Applicable
- Current Design Contract: JMT, Inc
- Construction Contractor: TBD
- Initial Construction Contract: TBD
- Current Construction Contract : TBD

Design Complete:	100%
Original Construction Completion:	0%
Construction Complete to Date:	0%
Current Construction Completion:	0%
Estimated Completion Date:	Dec 2008

Contact Information: John Veilleux, P.E. (352) 334-5070. Updated: 10-01-2008